

THE RAIN MAN

248203 5th Side Road, Mono
R. R. # 5, Orangeville, Ontario L9W 2Z2
Phone 519-941-5524 Fax 519-941-5951 Toll Free 800-461-7246
Cell 416-346-5709 Rick Middlebrook
therainman@on.aibn.com

August ---, 2007

Name:

I am pleased to submit the following quote for the provision of all material, labour and equipment to design and install an automatic sprinkler system for the above property, as per design. Price includes hook-up to a ¾" water supply in basement, capable of 10 GPM, and all necessary hardware to complete the system.

\$ 0,000.00 thousand hundred and dollars (plus GST).

MATERIALS

Sprinkler Heads:

1. Spray Heads	Hunter 4" spray heads	()
	Hunter adjustable S-type spray heads	()
	Hunter SRS series 12" hi pop-up	()
Bubblers:	Risers	()
2. Intermediate Rotor Heads	Hunter-Orbit PGJ series	()
	Hunter-Orbit PGM series	()
3. 40' radius heads	Hunter PGP series	()
	Rainbird Maxi Paw	()

Pipe:	Polyethylene 75 psi. various sizes ¾" 1" 1¼" 1½" 2"	(')
	P.V.C. Sdr 160 psi. various sizes 1½" 2"	(')

Controller:	Hunter Pro C (3 station)	(1)
	Hunter Pro C (3 station module)	()

Valves:	Orbit 57200 1" in line electric valve	()
	Orbit 57026 1½" in line electric valve	()
	Orbit 57211 Drip valve with filter & regulator	()

Boxes:	All valves housed in appropriate valve boxes	()
--------	--	--------

Sensor:	Mini Klik Rain Sensor	(1)
---------	-----------------------	-------

Other:	Supply & install all hardware, direct burial wire and conduits to complete system (beyond exterior walls). Approximate footage of conduit for walkways and drive.	(')
--------	---	----------

Drip Irrigation:	Netafim tech line .6 gph 12" spacing with filter, regulator and flow control valve.	(')
------------------	---	----------

* Price **does not include** a backflow preventer.

* Horizontal boring, if required (each bore \$20 per foot).

continued ...

TERMS

Contractor to supply all required material to complete the system.

Irrigation designed for 10 gpm. at 50 psi.

Client to make contractor aware of all buried utilities.

Client to provide a 110-volt receptacle for controller plug.

GUARANTEE

All products carry a manufacturer's warranty. All work is guaranteed for a period of one year from date of completion, for quality of workmanship and materials.

For the first year we will winterize the system in the fall and open the following spring. In future years there will be a nominal charge for these services.

Payment:	50% contract approval	\$ 1,000.00	+ GST
	50% balance on completion	\$ 1,000.00	+ GST
	Total	\$ 2,000.00	

Contract price is based on the supply of 00 sprinkler heads. This proposal is made on the basis of current material and labour costs. A delay in acceptance of more than 15 days will require a review of the proposal and redating before the agreement becomes binding (summer 2007 installation).

Respectfully submitted,

Rick Middlebrook

To complete the installation there will be _____ bores required under concrete driveway at a cost of \$400.00 per bore.

Acceptance: You are hereby authorized to furnish all materials and labour to complete the work described in the above proposal. The undersigned agrees to pay the amount in said proposal, and according to the terms thereof.

Date : _____ Signature: _____